

FTV-1 Negative Air Shutdown Condition

Negative Air Machine Shutdown

Case No. 1

ICR 56-7.8 (a) (1)

VARIANCE GRANTED. The Petitioner's proposal for shutting down the negative air system at the subject premises in accordance with the attached X-page stamped copy of the Petitioner's submittal, is accepted; subject to the Conditions noted below:

THE CONDITIONS

1. If negative air machines must be shut down at the end of each work day, the negative air machines must continue to run for a minimum of thirty minutes following completion of all abatement/cleaning activity for the day. Once the thirty-minute time period has elapsed, all accesses to the regulated abatement work area shall be sealed airtight, after all workers have exited the work area.
2. When re-establishing the work area in the morning, wait 30 minutes after the manometer reads a minimum of .02" of water pressure differential before entering the work area.
3. Usage of this variance is limited to those asbestos removals identified in this variance or as outlined in the Petitioner's proposal.